

DEPARTMENT OF HOMELAND SECURITY
UNITED STATES COAST GUARD
SHORE MAINTENANCECOMMAND

REVISED
SCOPE OF WORK
FOR
REPLACE PUBLIC WORKS SHOP

AT
U.S. COAST GUARD
SECTOR NORTH CAROLINA
ATLANTIC BEACH, NC

FEBRUARY 2011

COMMANDING OFFICER
UNITED STATES COAST GUARD
CIVIL ENGINEERING UNIT, RM 2179
1240 EAST NINTH STREET
CLEVELAND, OHIO 44199-2060

P/N 05-C05124
File: C7648X Revised

AUTHOR: L. L. Hersey, RA

REVISED

SCOPE OF WORK

1. WORK INCLUDED: Major items of work shall include the following:
 - 1.1 Work associated with these items is described in the specification sections, dated March 2010, and/or are shown on the contract drawings dated February 01, 2010. Incidental work items not listed above and necessary for completing the project shall be included. The general project scope is to design and construct a building to replace the Public Works Shop building that was torn down. Unless noted otherwise, work is generally confined to the existing Sector North Carolina site.
 - 1.2 The following Items of work are to be removed from the original Scope of work as specified and shown on the previously identified drawings. All other work to complete the building into a functional building shall be included.
 - 1.3 Work Items to be Eliminated From the Project Scope:
 - 1.3.1 Eliminate the Men's and Women's toilet rooms, including related plumbing, fixtures, electrical, walls, doors, and finishes. The ADA unisex toilet room with shower shall remain in the scope, including related plumbing, fixtures, electrical, walls, doors, and finishes.
 - 1.3.2 Eliminate from the Mezzanine: Eliminate 2 windows, all of the metal stud and drywall, acoustic suspended ceiling, floor and wall finishes. The wall at the edge of the Mezzanine to the High Bay shall remain in scope.
 - 1.3.3 Eliminate AHU 3 and HP 3 and related duct work. AHU 1 and AHU 2 and HP 1 and HP 2 shall remain in scope to service the areas above and under the mezzanine. Duct work for the mezzanine shall be a single supply duct with diffusers, suspended on the center line of the space at 9'-0" +/- AFF mezzanine floor. The return shall be a single duct with grills, located for good air flow.
 - 1.3.4 Eliminate Electrical outlets and data outlets from all of the Office walls that were eliminated. Provide one (1) 4" PVC conduit as shown for data cable to mezzanine. Provide two (2) duplex outlets on the remaining wall at the edge of the Mezzanine.
 - 1.3.5 Eliminate all of the lay-in fluorescent light fixtures from the mezzanine. Provide eight (8) 2 lamp 32W T8 fluorescent light fixtures suspended at 8'-0" AFF mezzanine floor.
 - 1.3.6 Make required adjustments to remaining work to accommodate the changes in scope.

End of Scope of Work