

**First Baptist Richlands**  
**Addendum # 2**  
**August 22, 2011**

The following addendum shall be acknowledged on the bid tab sheet.

1. The door hardware shall be burnished bronze.
2. The MRS system 1000 from Metal Roofing Systems is an accepted substitute for the Pac-clad roofing.
3. All wood doors are to be prefinished.
4. In Rooms 104 and 105 the wood floor is an engineered floor similar to Bruce.
5. The wood ceiling in room 137 is T&G Oak with V-Grooves.
6. Please see revised sheet M4.

End of Addendum #2.